


Description	Elevation (Ft.msl)	Depth (Ft.)	Area (S.F.)	Incl. Vol. (C.F.)	Total Vol. (C.F.)	Storage (Ac-Ft.)	Discharge (CFS)
	588.00	0.00	0	-	0	-	-
	588.50	0.50	452	113	113	-	-
	590.00	0.50	1,128	395	508	-	-
	591.00	1.00	1,209	1,168	1,675	-	-
2-Year	591.90	0.90	1,277	1,119	2,794	0.1	7.4
	592.00	0.10	1,284	128	2,922	-	-
	593.00	1.00	1,359	1,322	4,244	-	-
	594.00	1.00	1,427	1,393	5,636	-	-
10-Year	594.20	0.20	1,441	287	5,923	0.1	15.1
	595.00	0.80	1,489	1,176	7,099	-	-
25-Year	595.40	0.40	1,528	806	7,705	0.2	19.7
	596.00	0.60	1,572	930	8,635	-	-
WQSE	596.77	0.77	1,633	1,234	9,869	-	-
	596.78	0.01	5,659	36	9,905	-	-
100-Year	596.80	0.02	5,660	113	10,019	0.2	27.3
	597.00	0.20	5,677	1,134	11,152	-	-
500-Year	597.30	0.30	5,760	1,716	12,868	-	-

APPENDIX R-3				
PARTIAL SEDIMENTATION/FILTRATION POND CALCULATIONS FOR DEVELOPMENT PERMITS				
PATHWAYS AT GOODRICH PLACE, SP-2017-0503C.SH				
DRAINAGE AREA DATA:				
Corresponding Drainage Area(s)		P-1		
Drainage Area to Control (DA)		3.60	ac.	
Drainage Area Impervious Cover		78%		
Capture Depth (CD)		1.077	in	
WATER QUALITY CONTROL CALCULATIONS:				
		Required		Provided
The Water Quality Control is to be PARTIAL SEDIMENTATION FILTRATION				
25-year Peak Flow Rate to Control (Q25)	≥	22.30	cfs	25.26 cfs
100-year Peak Flow Rate to Control (Q100)		30.20	cfs	
Water Quality Volume (WQV=CD * DA* 3630)		14074	cf	14503 cf
Maximum Ponding Depth above Sand Bed (H)				3.74 ft
Sedimentation Pond Area				1419 sf
Sedimentation Pond Volume (≥20%WQV)	≥	2900.636	cf	4753 cf
Filtration Pond Area (WQV/(4 + 1.33*H))	≥	1616	sf	2607 sf
Filtration Pond Volume				9750 cf
Water Quality Elevation				596.77 ft msl
Elevation of Splitter/Overflow Weir	≥	596.77	ft msl	596.77 ft msl
Height of Gabion Wall		596.77	ft msl	596.77 ft msl
Gabion Wall under 6 ft (check)	≤	6.00	ft (max)	3.24 ft
Length of Splitter Weir				16.00 ft
Required Head to Pass Q ₁₀₀	≤	1.00	ft (max)	0.681 ft
Pond Freeboard Provided to Pass Q ₁₀₀	≥	0.250	ft (min)	0.299 ft
48 Hour Drawdown Time Orifice Opening diameter (inches)				1.125 in
Drawdown Time COA Calc. Avg. Head (min 48 hrs)	≥	48	hrs	50.00 hrs



* TOP OF GABION

DOUBLE WIDE
5.95' HIGH X 3' WIDE
GABION BASKETS

* BOTTOM OF GABION
AT POND

5.95' HIGH X
3' WIDE
GABION'S PER
CITY OF AUSTIN
STANDARD ROCK
SIZE 6" X 4" X 2"

2' WIDE CONCRETE
CONCRETE SPLASH
PAD 4" THICK
3000 P.S.I.

18" MIN.

ANCHOR GABION BASKET
TO #4 CORNER BARS

2' X 2' #4 CORNER BAR
AT 4 FEET O.C. (TYP.)

#4 BARS @ 8"
O.C.E.W.

SAND
FILTERS

NOTE:
AT EARTHEN FILL MATERIAL AT
POND BOTTOM, GABION SHALL BE WITHIN
95% OF MAXIMUM DENSITY.

SET BOTTOM OF GABION AT MIN. OF
12" BELOW FINISH GRADE ON THE
LOW SIDE OF THE GABIONS.

GABION MESH
(A) WOVEN MESH
WOVEN MESH SHALL BE OF A UNIFORM NON-RAVELING, DOUBLE
TWIST HEXAGONAL PATTERN NOMINALLY OF DIMENSIONS 3.25
INCHES BY 4.5 INCHES (83 MM BY 114 MM). SELVEDGE WIRE
SHALL BE 10 GAGS (NOMINAL DIAMETER OF 3.4 MM).

(B) WELDED MESH
MESH OPENING SHALL BE NOMINALLY 3 INCHES (75 MM BY 75
MM). STRENGTH OF WELDS SHALL MEET THE FOLLOWING
REQUIREMENTS WHEN TESTED IN ACCORDANCE WITH SECTION
13.4 OF ASTM A-974.

MINIMUM WELD STRENGTH REQUIREMENTS			
TYPE OF STRUCTURE	WIRE SIZE (DIAMETER)	MIN. AVERAGE WELD SHEAR STRENGTH	
	GAGE (MM)	ENGLISH UNITS (SI UNITS)	
GABIONS	12 (2.7)	472 LBF (2.10 kN)	
REVET MATTRESS	13.5 (2.2)	292 LBF (1.30 kN)	

(C) MANUFACTURING
TWISTED WIRE MESH GABION SHALL BE MANUFACTURED IN
CONFORMANCE WITH ASTM A-975, WHILE WELDED WIRE MESH
GABIONS SHALL BE MANUFACTURED IN CONFORMANCE WITH
ASTM A-974.

COA SPECIFICATION 5945

DRAWDOWN CALCULATIONS FOR A ROUND ORIFICE									
USING DYNAMIC HEAD									
PROJECT NAME: Pathways at Goodrich Place									
FILE PATH:									
V:\2202\active\c2220100556\Engineering\Design\pond\Subsurface\2018-03-05 WQ draw down.xls\Sheet1									
ORIFICE	1.1250 IN.		(1 1/8 IN. DRILL BIT)		W.Q Elev. =		14,503.18		CF
DIAMETER =					WQ Elev. =		596.77		MSL
CENTER OF					Top of Sand Elev =		593.03		MSL
ORIFICE =	588.72 MSL				Initial Head =		8.05		ft
					Final Head =		4.31		ft
TIME	HEAD	OUTFLOW	VOL.	dV	Total dV	H	dH		
HRS	FT	CFS	CF	CF	CF	FT	FT	FT	
0.00	8.05	0.09	14,503.18	339.56	339.56	3.65	0.09		
1.00	7.97	0.09	14,163.62	337.70	677.26	3.57	0.09		
2.00	7.88	0.09	13,825.92	335.85	1013.11	3.48	0.09		
3.00	7.79	0.09	13,490.07	334.00	1347.12	3.39	0.09		
4.00	7.71	0.09	13,156.06	332.15	1679.27	3.31	0.09		
5.00	7.62	0.09	12,823.91	330.30	2009.57	3.22	0.09		
6.00	7.53	0.09	12,493.61	328.45	2338.02	3.14	0.08		
7.00	7.45	0.09	12,165.16	326.60	2664.62	3.05	0.08		
8.00	7.37	0.09	11,838.56	324.75	2989.36	2.97	0.08		
9.00	7.28	0.09	11,513.62	322.90	3312.26	2.89	0.08		
10.00	7.20	0.09	11,190.92	321.04	3633.30	2.80	0.08		
11.00	7.12	0.09	10,869.88	319.19	3952.49	2.72	0.08		
12.00	7.03	0.09	10,550.69	317.34	4269.84	2.64	0.08		
13.00	6.95	0.09	10,233.34	315.49	4585.33	2.56	0.08		
14.00	6.87	0.09	9,917.85	313.64	4898.96	2.48	0.08		
15.00	6.79	0.09	9,604.22	311.79	5210.75	2.40	0.08		
16.00	6.71	0.09	9,292.43	309.94	5520.69	2.32	0.08		
17.00	6.63	0.09	8,982.49	308.08	5828.77	2.24	0.08		
18.00	6.55	0.09	8,674.41	306.23	6135.00	2.16	0.08		
19.00	6.47	0.08	8,368.18	304.38	6439.38	2.08	0.08		
20.00	6.39	0.08	8,063.80	302.53	6741.91	2.00	0.08		
21.00	6.31	0.08	7,761.27	300.68	7042.59	1.92	0.08		
22.00	6.24	0.08	7,460.59	298.83	7341.41	1.85	0.08		
23.00	6.16	0.08	7,161.77	296.97	7638.39	1.77	0.08		
24.00	6.08	0.08	6,864.79	295.12	7933.51	1.69	0.08		
25.00	6.01	0.08	6,569.67	293.27	8226.78	1.62	0.08		
26.00	5.93	0.08	6,276.40	291.42	8518.20	1.54	0.08		
27.00	5.86	0.08	5,984.98	289.57	8807.77	1.47	0.07		
28.00	5.78	0.08	5,695.41	287.71	9095.48	1.39	0.07		
29.00	5.71	0.08	5,407.70	285.86	9381.34	1.32	0.07		
30.00	5.63	0.08	5,121.84	284.01	9665.35	1.25	0.07		
31.00	5.56	0.08	4,837.83	282.16	9947.51	1.17	0.07		
32.00	5.49	0.08	4,555.67	280.31	10227.82	1.10	0.07		
33.00	5.42	0.08	4,275.36	278.45	10506.27	1.03	0.07		
34.00	5.34	0.08	3,996.91	276.60	10782.87	0.96	0.07		
35.00	5.27	0.08	3,720.31	274.75	11057.62	0.89	0.07		
36.00	5.20	0.08	3,445.56	272.90	11330.52	0.82	0.07		
37.00	5.13	0.08	3,172.66	271.05	11601.57	0.75	0.07		
38.00	5.06	0.07	2,901.61	269.19	11870.76	0.68	0.07		
39.00	4.99	0.07	2,632.42	267.34	12138.10	0.61	0.07		
40.00	4.92	0.07	2,365.08	265.49	12403.59	0.54	0.07		
41.00	4.85	0.07	2,098.96	263.64	12667.22	0.47	0.07		
42.00	4.79	0.07	1,835.98	261.78	12929.01	0.41	0.07		
43.00	4.72	0.07	1,574.17	259.93	13188.94	0.34	0.07		
44.00	4.65	0.07	1,314.24	258.08	13447.01	0.27	0.07		
45.00	4.59	0.07	1,056.17	256.23	13703.24	0.21	0.07		
46.00	4.52	0.07	799.94	254.37	13957.61	0.14	0.07		
47.00	4.45	0.07	545.57	252.52	14210.13	0.08	0.07		
48.00	4.39	0.07	293.05	250.67	14460.80	0.01	0.06		
49.00	4.32	0.07	42.38	248.81	14709.61	-0.05	0.06		
50.00	4.26	0.07	0.00	246.96	14956.57	-0.12	0.06		

8

Know what's below.
Call before you dig.

FOR CITY USE ONLY:

THE LOCATION OF EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE WAY ONLY. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK. HE AGREES TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE OCCASIONED BY HIS FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES.

STATE PLANT APPROVAL Sheet 32 of 37

FILE NUMBER: 08-091-00808-1 APPLICATION DATE: 08/08/08 11 MAY
RECEIVED BY COMMISSION ON 7/21/08 UNDER SECTION 118 OF
CHAPTER 28 OF THE CITY OF AUSTIN CODE.
EXPIRATION DATE (28-5-81, LDC) 7/21/12 CASE MANAGER C. DAVIS
PROJECT EXPIRATION DATE (ORD.#0776005-4) DWPE DVOZ

OK

Director, Development Services Department

RELEASED FOR COMMISSION COMPLIANCE: ZONING: 08-01-00

Rev. 1 _____ Correction 1 _____
Rev. 2 _____ Correction 2 _____
Rev. 3 _____ Correction 3 _____

FINAL PLAT MUST BE RECORDED BY THE PROJECT EXPIRATION DATE, IF APPLICABLE. SUBSEQUENT SITE PLANS WHICH DO NOT COMPLY WITH THE ORD CURRENTLY AT THE TIME OF FILING, AND ALL REVISED BUILDING PERMITS AND/OR A NOTICE OF CONSTRUCTION (IF A BUILDING PERMIT IS NOT REQUIRED), MUST ALSO BE APPROVED PRIOR TO THE PROJECT EXPIRATION DATE.